



Implemented measures at the border stretch of River Mur since 2002

DI Oliver Rathschüler Managing Director freiland Ziviltechniker GmbH, Wien - Graz







Activities

- 1995: First baseline surveys
- 1998 2001
 Principaled Water Management Concept PWMC 2001
- 2002 2013
 Planning & Implementation of measures







Main objectives PWMC 2001 and others

- Prevention of further deepening by stabilisation of the riverbed and the groundwater balance
- Flood protection non-technical water retention measures
- Restoration of natural river structures and habitats
- Re-activation and free migration of tributary streams
- Creation of dynamic river- and alluvial habitats
- Preservation and enhancement of the "NATURA 2000" EU-wide network
- Enhancement of accesibility and public awareness
- Bilateral cooperation and inclusion of all relevant stakeholders







Implemented measures AT-SI

River MUR (14 measures)

River widening Oberschwarza (2004) River widening Weitersfeld (2005) River widening Donnersdorf (2006-2007) River widening Gosdorf I (2006-2007), Widening Gosdorf II (2013) River widening Sicheldorf (2012) River widening Estuary Breuss-Lahn (2012) Fish pass Spielfeld & Estuary Gamlitzbach (2006-2009) River restructuring Bad Radkersburg (2005-2007) Cross-border river attraction– Skupaj (2010-2014) *Side arm connection Alter Graba (2012) Widening Segovci Flood wall construction,*

Flood levee reconstruction Gornja Radgona (in preparation)

Tributaries and back waters (13 measures) Flow donation mill-stream Mureck-Radkersburg (2000-2001) Flow donation mill-stream Straß-Lichendorf Flow donation Wäschbach (2002-2003) Flow donation Trummerbach-Lahn (2007) Flow donation Schwarzaubach (2008) Fish pass Gnasbach – Feilbach (2006) Fish pass & Flow diversion Ruppmühle (2006-2007) Restoration Saßbach (2004) Restoration Tischler pond (2005) Restoration Glauningbach (2007) **Restoration Kutschenitza** Pond habitat Perbersdorf (2006) Enajstmlinski mill channel (2012)













Measures of PMWC 2001 monitoring & surveys 1

Riverbed monitoring

- Constant measurement of selected cross-sections between km 95,00 and approx. km 130,00
- 07/2009: Interim report "Morphodynamic analysis of river-widenings and lateral erosion at Border Mura" covering widening Gosdorf and Donnersdorf
- 06/2013: Report "Sediment and suspended sediment monitoring, sediment-transport and lateral erosion at Border Mur"
- 04/2016: Report "Significance of river-engineering measures for the groundwater at Border Mur" "..., it is proven, that the river-engineering measures between Spielfeld and Bad Radkersburg initiated the stabilization of the river-bed resp. initiated a raising of the river bed level"

Groundwater

 2005 and 2012: Studies on possible effects of river-widenings concerning the public wells near Gosdorf I (2005) and Gosdorf II (2012)







Measures of PMWC 2001 monitoring & surveys 2

Habitats monitoring

- 05/2008: 1st monitoring of river-widening Gosdorf I
- Other habitat-monitorings are cited, have not yet been found (e.g. general forest survey)

Species monitoring

- 02/2013: Zoological monitoring in the river-widenings Gosdorf I and Donnersdorf (birds, ground beetles, dragonflies)
- Styrian Government: Fish monitoring "Motorway bridge Spielfeld": 2007, 2010, 2013
- Styrian Government: Fish monitoring "Radkersburg": 2007, 2010, 2016
- 10/2009: Spielfeld Power-station, survey on the fish pass and it's functionality







N2000 Baseline 2004 in the area

N2000 Management Plan "Measures" of 2004

- Covers the "Border Mur" river stretch
- Comprises 5 chapters of measures:
 - Water: measures of PWMC and other measures (backwaters, ponds etc.)
 - Forestry
 - Agriculture
 - Protected species according to FFH-Directive
 - Visitors guidance

N2000 MMP "Measures" of 2004 bases on

- 2003/2004 Survey on Fish population in N2000 covering the area of Border Mura including Gamlitzbach and Gnasbach
- 2004 "MMP N2000 area Border Mura including Gamlitzbach and Gnasbach" baseline surveys and proposed measures dealing with
 - <u>Habitats</u> according to appendix I FFH-Directive
 - <u>Species</u> according to appendix II FFH-Directive
 - <u>Birds</u> according to appendix I Birds-Directive







Evaluation/Monitoring

Riverbed monitoring

- constant cross-section survey
- analysis of bed-load discharge
- maintenance work of widenings

Overall, it can be stated that the measures fulfil their functions - a dynamic course of the river and embankments is in process. Except measure Gosdorf I is limited in it's functionality.

- Nature 2000 monitoring
 - fish- ecological assessment
 - extensive monitoring combined with habitat modelling and an investigation of different types of biotopes and animal species, visitor pressure and invasive special

The monitoring results show a striking development of already existing and new habitats of the examined protective goods concerning the realization of measures.







River widenings









River widening Oberschwarza









River widening Oberschwarza

Objectives

- Counteracting river-bed erosion
- Promoting gravel mobilization
- Enhancement of (hydro-)morphology and fish ecology

Implemented measures

- River bank protection removal along 300 m
- Creation of a side branch of 400 m length thereby establishing an island in the river

Recent development

- Good functionality: constant discharge in river side branch, no siltation tendency
- Strong dynamic around the river island as this river section is not secured by bank protection measures







River widening Weitersfeld











River widening Weitersfeld

Objectives

- Counteracting river-bed erosion
- Promoting gravel mobilization
- Enhancement of (hydro-)morphology and fish ecology

Implemented measures

- River widening river bank protection removal along 500 m
- Creation of a side branch of 600 m length

Recent development

Good functionality: constant discharge in river side branch, no siltation tendency







River widening Gosdorf I





Mur-Tower Estuary Sassbach







THE

FUTURE

River widening Gosdorf I







BORDER MURA BILATERAL CONFERENCE Radenci, Slovenia 8. - 9. May 2019

Source: Google Earth Pro







River widening Gosdorf II











River widening Gosdorf I & II

Objectives

- Counteracting river-bed erosion Promoting river bank erosion / gravel mobilization
- Enhancement of (hydro-)morphology and fish ecology
- Attractivation for recreational visitors

Implemented measures

- River widening river bank protection removal along 1000 m (Gosdorf I)
- Creation of a side branch establishing natural river banks (Gosdorf I)
- Initiation of a Bumblebee habitat (Gosdorf I)
- Construction of an observation tower (Gosdorf I)
- Creation of a 900 m length-side branch (tied to the main river downstream), additional discharge in the case of flood events (Gosdorf II)

Recent development

- Gosdorf I: Functionality not sufficiently established: strong siltation tendency as the side branch is connected to the main river right-angled (due to limited availability of land). Deposited gravel had to be dredged three times since implementation
- Gosdorf II: Good functionality, no siltation constant discharge







River widening Donnersdorf









River widening Donnersdorf

Objectives

- Counteracting river-bed erosion
- Promoting gravel mobilization
- Development of a natural river-shore
- Re-connecting of a tributary (Feilbach)

Implemented measures

- River widening and river bank protection removal along 300 m
- Creation of a 400 m side branch
- Widening estuary Feilbach, establishing passable estuary
- Creation of a Jetty/ boat dock

Recent development

- Constant discharge in river side branch, no siltation tendency
- Subsequent modification of the jetty was necessary







River widening Sicheldorf











River widening Sicheldorf

Objectives

- Counteracting river-bed erosion
- Promoting gravel mobilization
- Creation of retention areas for floods

Implemented measures

- Widening on a length of about 1.400m by initial erosion scars for river widening (bays, excavation of 15,000 m³)
- Removal of bank protection

Recent development

- Very dynamic system, shift of the border (gravel bar in Slovenia, River bank dynamics on Austrian side)
- Protection of adjacent properties necessary due to high river dynamics
- Neophytes in high numbers









Flow donation mill-stream Straß-Lichendorf









Flow donation mill-stream Straß-Lichendorf

Objectives

- Establishing connectivity and constant flow to a formerly dried-up side channel of the Mur
- Irrigation of agricultural areas
- Enhancement of groundwater situation

Implemented measures

• Constant discharge for the Mühlbach (800 l/s) from the HPP Spielfeld

Recent development

• Good functionality established







Fish pass HPP Spielfeld, Gamlitzbach











Fish pass HPP Spielfeld, Gamlitzbach

Objectives

- Enabling upstream migration/longitudinal connectivity (Mur, Gamlitzbach)
- Establishing new valuable fish habitats

Implemented measures

- Construction of a 3 km long, nature-like bypass channel (which incorporates the tributary Gamlitzbach)
- Construction of a technical fish-pass (Vertical-Slot)
- Re-design of Gamlitzbach estuary

Recent development

- Fish pass functionality confirmed
- New habitats for fish established
- Increase in fish species shortly after implementation







Enajstmlinski mill channel











Enajstmlinski mill channel

- The longest (only) mill channel on Slovene side of the border Mura (cca 17 km)
- High local interest (Apače Municipality) and good cooperation of local and national authorities (municipality DRSV)
- Executed measures:
 - Channel clearing of sediment and vegetation (DraMurCl and Apače municipality funds)
 - Discharge analsis (numerical hydraulic modeling) and
 - Groundwater analysis: levels (flooding of certain basements) and flow patterns (drinking water quality)
- Recent development:
 - Pilot activity of water inflow carried out in september 2018
 - Flow monitoring at 18 sections of the stream and groundwater level monitoring at all 20 endangered objects
 - Pilot activity stopped after few days
 - Results: need for reconstruction of channel at Žiberci
- Current development:
 - Channel reconstructed and awaiting continuation of the pilot
- Future development:
 - Pilot activities will give insight to possible negative impacts (endangered objects, groundwater flow pattern)
 - Planed activities: reconstruction of inflow and outflow objects, securing sufficient levels on Mura at inflow, measures to reduce possible negative impacts (if needed)











THE FUTURE OF BORDER BORDER MURA BILATERAL CONFERENCE Radenci, Slovenia 8. - 9. May 2019

SLOVENIJA - AVSTRIJA SLOWENIEN - ÖSTERREICH

Evropska unija | Evropski sklad za regional Europäische Union | Europäischer Fonds für regionale E







Flow donation Trummerbach-Lahn

Objectives

- Establishing constant flow from Sulzbach
- River protection (crossings)
- Preservation of existing water-bound meadows

Implemented measures

- Flow donation through a intake structure at the Sulzbach (technical construction with slice gate)
- Securing of stagnant waters
- Construction of river-crossings instead of using riffles

Recent development

- Functionality not sufficiently established
- Strong siltation tendency deposited gravel needs regular dredging.





Widening Breuss-Lahn











Widening Breuss-Lahn

Objectives

- Enhancement of (hydro-)morphology and fish ecology
- Counteracting river-bed erosion

Implemented measures

- River widening estuary Breuss-Lahn (size: 1 ha)
- Creation of a jetty
- River widening Mur (37 m width)

Recent development

- Near-natural development
- Siltation tendencies at the boat deck







THANK YOU!

DI Oliver Rathschüler freiland Ziviltechniker GmbH, Wien – Graz

o.rathschueler@freiland.at +43 (0)1 310 79 70





